

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

DRM/Engineering acting for and on behalf of The President of India invites E-Tenders against Tender No **152-25-26** Closing Date/Time 29/09/2025 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Provision of 3 m wide FOB at Kesrisinghpur station of Bikaner Division under ADEN/Hanumangarh-II		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	29/09/2025 15:00	Date Time Of Uploading Tender	03/09/2025 16:21
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	22379665.77	Tendering Section	NORTH
Bidding Style	Single Rate for Each Schedule	Bidding Unit	
Earnest Money (Rs.)	261900.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	8 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	15/09/2025		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () A-CPWD DSR items							17369318.29	Above/ Below/Par
1	Please see Item Breakup for details.			6917333.10	(-) 38.00	4288746.52		
	Description:- All items of "Concrete Work and Reinforced cement concrete" appearing in Chapter No. 04 & 05 of CPWD DSR (Amended up to date)							
2	Please see Item Breakup for details.			18875425.00	(-) 38.00	11702763.50		
	Description:- All items of "Steel Work" appearing in Chapter No. 10 of CPWD DSR (Amended up to date)							
3	Please see Item Breakup for details.			2222271.40	(-) 38.00	1377808.27		
	Description:- All items of "All other chapters" of CPWD DSR (Amended up to date) except mentioned above.							
S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () B-IRUSSOR 2021 items							5010347.48	Above/ Below/Par
1	Please see Item Breakup for details.			4793807.74	AT Par	4793807.74		
	Description:- All items of " Bridge Works : Super Structure -Steel" appearing in Chapter No. 04 of IRUSSOR (Amended up to date)							
2	Please see Item Breakup for details.			216539.74	AT Par	216539.74		
	Description:- All items of "All other chapters" of IRUSSOR (Amended up to date) except mentioned above.							

3. ITEM BREAKUP

Schedule	Schedule A-CPWD DSR items
Item- 1	All items of "Concrete Work and Reinforced cement concrete" appearing in Chapter No. 04 & 05 of CPWD DSR (Amended up to date)

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
1	4.1.2	1:1.5:3 (1 Cement: 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	42	7783.65	326913.3
2	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	35	7365.15	257780.25
3	4.1.8	1:4:8 (1 Cement : 4 coarse sand (zone-III) derived from natural sources : 8 graded stone aggregate 40 mm nominal size derived from natural sources)	cum	21	6326.05	132847.05
	5.0	REINFORCED CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
4	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	435	307.95	133958.25
5	5.9.3	Suspended floors, roofs, landings, balconies and access platform	Sqm	580	766.55	444599
6	5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	100	804.25	80425
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
7	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	14500	89.65	1299925
	5.22A	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level.				
8	5.22A.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	14500	89.65	1299925
	5.33S	DESIGN MIX CONCRETE				

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

	5.33	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate /retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the engineer-in-charge; for the following grades of concrete. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 1.10 times of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.				
	5.33.1	All works upto plinth level				
9	5.33.1.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	150	8683.8	1302570
	5.33.2	All works above plinth level upto floor V level				
10	5.33.2.1	Concrete of M25 grade with minimum cement content of 330 kg /cum	cum	85	10306.2	876027
11	5.33.2.2	Concrete of M30 grade with minimum cement content of 350 kg /cum	cum	15	10477.75	157166.25
12	5.33.2.3	Concrete of M35 grade with minimum cement content of 370 kg /cum	cum	50	10589.35	529467.5
13	5.35	Add for using extra cement in the items of design mix over and above the specified cement content therein.	Quintal	110	688.45	75729.5
					Total	6917333.10
Item- 2	All items of "Steel Work" appearing in Chapter No. 10 of CPWD DSR (Amended up to date)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	10.0	STEEL WORK				
1	10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	500	93.05	46525
2	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	60000	111.95	6717000
	10.16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
3	10.16.1	Hot finished welded type tubes	Kg	65000	154.9	10068500
4	10.19	Providing and fixing mild steel round holding down bolts with nuts and washer plates complete.	Kg	1700	88.5	150450
	10.25	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.				

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

5	10.25.2	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	9000	142.3	1280700
6	10.28	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	Kg	1000	612.25	612250
					Total	18875425.00
Item- 3	All items of "All other chapters" of CPWD DSR (Amended up to date) except mentioned above.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	2.0	EARTH WORK				
	2.8	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
1	2.8.1	All kinds of soil.	cum	700	286.85	200795
2	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	350	253.95	88882.5
	2.26	Extra for every additional lift of 1.5 m or part thereof in excavation / banking excavated or stacked materials.				
3	2.26.1	All kinds of soil	cum	350	104.5	36575
	6.0	MASONRY WORK				
	6.1	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in:				
4	6.1.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	14	6658.25	93215.5
	6.4	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :				
5	6.4.2	Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	14	8288.35	116036.9
	8.0	CLADDING WORK				
	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels.				

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

	8.2.2	Granite stone slab of colour black, Cherry/Ruby red				
6	8.2.2.2	Area of slab over 0.50 sqm	Sqm	69	4425.35	305349.15
	11.0	FLOORING				
	11.16S	TILE FLOORING				
	11.20	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).				
7	11.20.4	Ordinary cement without any pigment	Sqm	450	928.5	417825
	11.26S	KOTA STONE FLOORING				
	11.26	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :				
8	11.26.1	25 mm thick	Sqm	150	1706.6	255990
	12.0	ROOFING				
	12.42	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion.				
9	12.50	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	450	671.55	302197.5
	12.51	Providing and fixing precoated galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/ self tapping screws complete :				
10	12.51.1	Ridges plain (500 - 600mm)	Metre	104	450.6	46862.4
	13.0	FINISHING				
	13.1S	CEMENT PLASTER (IN FINE SAND)				
	13.2	15 mm cement plaster on the rough side of single or half brick wall of mix :				
11	13.2.2	1:6 (1 cement: 6 fine sand)	Sqm	138	324.3	44753.4
	13.3	20 mm cement plaster of mix :				
12	13.3.2	1:6 (1 cement: 6 fine sand)	Sqm	345	382.1	131824.5
	13.63	Painting with aluminium paint of approved brand and manufacture to give an even shade .				

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

13	13.63.1	Two or more coats on new work	Sqm	500	121.45	60725
	15.0	DISMANTLING AND DEMOLISHING				
14	15.18	Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50 metres lead.	Kg	1000	4.65	4650
	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
15	15.23.2	For thickness of tiles above 25 mm and up to 40 mm	Sqm	166	93.4	15504.4
16	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	cum	69	219.35	15135.15
	16.0	ROAD WORK				
	16.49S	MISCELLANEOUS				
17	16.90	Providing and laying tactile tile (for vision impaired persons as per standards) of size 300x300x9.8mm having water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	Sqm	50	1719	85950
					Total	2222271.40
Schedule	Schedule B-IRUSSOR 2021 items					
Item- 1	All items of " Bridge Works : Super Structure -Steel" appearing in Chapter No. 04 of IRUSSOR (Amended up to date)					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
		Supplying, fabrication, assembling of all types of steel girders of specified spans with structural steel conforming to Quality "BO" Grade Designation E250 conforming to IS:2062, erection / slewing / end launching of steel girders with cranes or any other approved launching methods as per site conditions (not requiring traffic block) on sub-structure including provision of trolley refuges etc., complete as per approved Q A P and drawings conforming to IRS-B1-2001 and other relevant codes and specifications. Note: 1. Detailed fabrication and erection drawings & launching methodology will be prepared by the contractor and got approved from Railway. 2. The rate is all inclusive including launching in position, complete in all respect except cost of (i) Painting / Metalising; (ii) Bearings & (iii) HSFSG bolts which shall be paid extra under relevant item. 3. The payment shall be made on the theoretical weight of main components and gusset plates only. 4. Payment Schedule: (i) Receipt of material at site: 40% (ii) Fabrication of girders: 20% (iii) Erection/Launching: 20% (iv) Completion in all respects: 20%				

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

1	041011	Plate Girder/Semi Through Girder/Composite Girder (Steel Work)	MT	28.00	138069.16	3865936.48
2	041013	Extra for using steel conforming to Grade Designation E350 instead of Grade Designation E250 of Quality "B0" as per IS: 2062	MT	28.00	4722.92	132241.76
3	041020	Supplying and fixing HSFG bolts of any dia and any length with suitable nuts including DTI washers conforming to IRS-B1-2001 for bridges and steel structures with contractors labour, tools and plants and lead and lift etc., complete.	Kg	3550.00	180.45	640597.50
		Metallizing of steel work of girders with sprayed aluminium after surface preparation by Sand/grit blasting, followed by one coat of etch primer (IS:5666) & one coat of Zinc Chrome primer (IS:104) and two coats of aluminium paint (IS:2339) with all labour, T&P and material as a complete job duly conforming to all relevant specifications and process given under Clause 39 of IRS-B1-2001. Note: Nominal Thickness of sprayed Aluminium coating shall be 150 microns. DFT of Zinc chrome primer shall be 25-30 microns and DFT of each coat of Aluminium paint shall be 12-14 microns.				
4	041041	On new girder during fabrication	Sqm	200.00	775.16	155032.00
					Total	4793807.74
Item- 2	All items of "All other chapters" of IRUSSOR (Amended up to date) except mentioned above.					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
		Exploratory drilling of boreholes down to required depth, drilling of 150mm dia. boreholes in all type of soils except hard rock & large boulders (boulder core more than 30cm) including refilling, reinstating surface and disposing off surplus material including use of mechanical rigs with power operated winches as well as percussion/chiselling tool for advancing through occasional seams of hard strata to be employed, where necessary in Dry area.				
1	021011	0m to 10m	Metre	40.00	1300.48	52019.20
2	021110	Taking out 100mm dia. & 450mm long undisturbed samples of soil from bore holes, including provision of air tight containers for packing and, labeling incl. transporting the samples to laboratory. Piston sampler shall be used for extracting undisturbed samples where necessary. Samples shall be collected as per IS:2720.	Each	2.00	152.52	305.04
3	021120	Taking out 100mm dia. & 450mm long disturbed samples of soil from bore holes, including provision of air tight containers for packing, labeling and transporting the samples to laboratory. Samples shall be collected as per IS:2720.	Each	2.00	164.57	329.14
4	021130	Conducting standard penetration test as per IS:2131 at approximate 1.5m intervals in bore holes, as directed by the Engineer in charge	Each	2.00	852.27	1704.54
		Conducting laboratory Tests on collected soil samples as per relevant IS code				
5	021151	Moisture Content/Dry Density	Each	2.00	287.66	575.32
6	021152	Atterberg Limits	Each	2.00	586.02	1172.04
7	021153	Specific Gravity	Each	2.00	631.51	1263.02
8	021154	Grain size analysis including Hydrometer analysis	Each	2.00	727.84	1455.68

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

9	021155	Direct Shear Test	Each	2.00	2330.69	4661.38
10	021156	Natural Density	Each	2.00	674.32	1348.64
11	021157	Consolidation Test	Each	2.00	6886.37	13772.74
12	021158	Unconfined Compression Test	Each	2.00	2006.91	4013.82
13	021159	Tri-axial Test	Each	2.00	2158.09	4316.18
		Hiring of machinery for minor miscellaneous works for short duration including operator/driver, fuel, lubricants and consumable. The contractor shall arrange all statutory permits as required by rules and regulations prevailing in the area of work. Payment shall be made for actual working hours at site.				
14	211201	JCB Backhoe Loaders 3DX Plus or similar with minimum 1.10 cum bucket capacity	Hour	150.00	864.02	129603.00
					Total	216539.74

4. ELIGIBILITY CONDITIONS

Standard Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Financial Eligibility Criteria: The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB, along with copies of Audited Balance Sheets duly certified by the Chartered Accountant/ Certificate from Chartered Accountant duly supported by Audited Balance Sheet. Note :- (i) For Joint Venture (JV): The tenderer shall submit credentials as mentioned in Clause 17 of GCC April 2022 (Ammended upto date). (ii) In case, date of tender inviting is on or after date of statutory deadline for audit of balance sheet of previous Financial Year (i.e. 30th Sept. or as further extended for this FY), audited balance sheet of 4th previous year shall not be considered unless concerned CA certifies that balance sheet is not audited yet as on date of invitation of this tender.	No	No	Allowed (Mandatory)

Standard Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have successfully completed or substantially completed any of the following during last 07 (seven) years, ending last day of month previous to the one in which tender is invited: (a) Three similar works costing not less than the amount equal to 30% of advertised value of the tender, or (b) Two similar works costing not less than the amount equal to 40% of advertised value of the tender, or (c) One similar work costing not less than the amount equal to 60% of advertised value of the tender. Note :- For Joint Venture (JV): The tenderer shall submit credentials as mentioned in Clause 17 of GCC April 2022 (Ammended upto date).	No	No	Allowed (Mandatory)
1.1	Defination of Similar Work :- Fabrication of steel structures	No	No	Not Allowed

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	1.The quantities/amount mentioned above are rough and for guidance only and are subject to change according to the needs of the railway & variation there of to any extent will not be the basis of any claim against the Railway. 2.The work shall be carried out as per standard specifications (Amended up to date). 3.The contract shall be governed by General Condition of Contract and Instructions to the Tenders -2022 (Amended up to date). 4.All tools & plants and mechanical equipment as required to execute the work shall be arranged by the contractor. 5.Contractors/ suppliers/ service providers/ parties shall register their firms under EPFO & GSTIN (GST Identification Number).	No	No	Not Allowed

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
-------	-------------	-----------------------	-----------------	---------------------

**BIKANER DIVISION-ENGINEERING/NORTH WESTERN RLY
TENDER DOCUMENT**

Tender No: 152-25-26

Closing Date/Time: 29/09/2025 15:00

1	I/We also understand that if the contents of the documents submitted by us are found to be false/ forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance Guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.	No	No	Not Allowed
2	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)	No	No	Not Allowed
3	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed

Custom

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderers shall submit a copy of certificate as detailed in related Para no. 11(vii) of General Condition as Annexure -A-1A. Performa of certificate is enclosed in general condition.	No	No	Allowed (Mandatory)
2	The tenderer shall submit copy regarding status of firm i.e. sole proprietorship, partnership, Company, Society/Trust etc. and also submit a power of attorney as detailed in related Para no. 13 of General Condition.	No	No	Allowed (Mandatory)

6. Documents attached with tender

S.No.	Document Name	Document Description
1	Generalcondition23.04.25From12-25-26_compressed.pdf	General condition
2	GCC-2022-uptoACS104.3.25.pdf	GCC April 2022 upto ACS10 updated

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: NEERAJ SINGH YADAV

Designation : DENNorth